



Provide temporary support, cut out studs
 Add new 4x6 header, tight fit to underside of existing studs (min)

Add 2x4 cripple (min) - 16d @ 16"
 Add full length 2x4 stud from sill to top plate

- NOTE UNLESS OTHERWISE SPECIFIED
- 1 DIMENSIONS HAVE PREFERENCE OVER SCALE
 - 2 CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS AT EACH JOB SITE
 - 3 ALL PHASES OF CONSTRUCTION SHALL COMPLY WITH THE CURRENT EDITION OF THE IBC AND/OR STATE AND LOCAL CODES
 - 4 CONTRACTOR SHALL SECURE AND PAY FOR ALL PERMITS REQUIRED BY THE ORANGE COUNTY DEPARTMENT OF BUILDING AND SAFETY & PROFESSIONAL COMMUNITY MANAGEMENT INC
 - 5 UPON COMPLETION CONTRACTOR SHALL REMOVE ALL DEBRIS AND EXCESS MATERIALS AND LEAVE ALL AREAS OF WORK BROOM CLEAN
 - 6 SLIDING GLASS DOOR TYPE, STYLE AND HARDWARE SHALL MATCH EXISTING OR BETTER QUALITY
 - 7 SLIDING DOORS SHALL HAVE GLASS OF LAMINATED SAFETY FULLY TEMPERED OR WRE GLASS

PARTIAL PLAN VIEW 1/4" SCALE

VERTICAL FRAMING - KNO GRADE OR BETTER
 HORIZONTAL FRAMING - *2 DFL. 1 OR BETTER

NOTE:
 IF DIAGONAL BRACE IS CUT SHEAR PANEL MUST BE INSTALLED MINIMUM DIMENSIONS 5/16' x 4' x 8' PLYWOOD 8d @ 6" cc @ PERIMETER



(70 392)
EL DOBLE (46 plan) SLIDING GLASS DOOR DINING ROOM
STANDARD PLAN NUMBER 141
PROFESSIONAL COMPATILITY MET INC APPROVED
PCM INC. 380-4516 P.O. BOX 2220 LAGUNA HILLS